File No. 1024
1935.

Collection No.

(W)

Mysore Residency

Pros. Serial Nos. 1 — 1,-8

Subject.

Grant to Baldwin School.
Opening of a Swimming Pool.

Previous References.

X. No. 53 of 1932

Later References.

1403-36.
R. dis. 479-35

S. 97.—(Blue).

MFP—1367 S&P—(M-1907)—8-3 35—60,000.

1024
37

THE RESIDENCY,
BANGALORE.

Mr. Weston, Ladies and Gentlemen,

My remarks will be very brief for I am sure that you are all impatient to see the Swimming Pool.

I consider it an honour to have been invited to open the Pfeiffer Swimming Pool; and it has been a real pleasure to me to be present here this evening, for I have a great admiration for the manner in which this School is playing its part in the education and the formation of character of boys of the Civil and Military Station under the devoted charge of Mr. Weston who is so ably assisted in his work by Mrs. Weston.

I have already been behind the scenes; in other words I have already seen the pool; and I may say at once that I agree that it is a very fine one and that I consider that the management and the boys of this School are under a great debt of gratitude to all those people who have so generously contributed towards the cost of its construction. The

pool

The pool is a credit to all those who have had a hand in its planning and construction.

Mr. & Mrs. Pfeiffer and Bishop & Mrs. Oldham have indeed been good friends to the School; and the support which the local residents have always given to the School has been very encouraging and most praiseworthy.

In his address Mr. Weston has made an appeal for funds to enable the School to complete its plans for providing vocational training. The total amount still required for this purpose is only Rs.500/-. In supporting his appeal, which I feel confident will meet with a generous response, I might mention that Government, recognising the importance of vocational training, is itself making a grant to the School for the purpose.

The Pfeiffer Swimming Pool

TO THE HON'BLE

LT.-COL. C. T. C. PLOWDEN, C.I.E.,

RESIDENT IN MYSORE

DEAR SIR,

WE are assembled here this evening to witness the inauguration of the Pfeiffer Swimming Pool. Before asking you to formally declare it open, I would like, Sir, on behalf of the Baldwin Boys' High School, to thank all those who have had a share in the consummation of this beautiful structure and to add a few remarks in general.

I wish Mr. and Mrs. Henry Pfeiffer of New York could have been present on this occasion to see the happy expectant faces of our boys who have been dreaming of this Pool for some time. We thank God and the Oldhams for establishing the friendly contact between the Pfeiffers and the Baldwin Boys' High School. Mr. and Mrs. Pfeiffer paid $5,000 into the funds of this School in 1933 and early this year they sent us $1,000 towards the cost of this Pool. Baldwinians will never forget the debt we owe these dear people.

Mr. and Mrs. Pfeiffer have paid more than half the cost of this Pool. The balance of the funds have been obtained from Parents, Old Boys and Friends of the School. The Fancy Sale held in 1934 yielded over Rs. 1,000. Our grateful thanks are due to all those who have responded to our Appeals. Our most generous donors are Bishop W. F. and Mrs. Oldham. Amongst the Parents Mr. C. Amos has helped most liberally. Mr. Cecil Eagles heads the list of contributors from amongst Old Boys.

Mr. G. T. Bridges is the Engineer who drew up the original plans of the Pool. He also supervised and watched its construction on behalf of the School. Mr. Gardener, of the Railway and General Engineering Company, is the Architect and "Reinforced Concrete Expert" to whose skill we owe a great deal. He has had a vast experience in this type of work and we were indeed fortunate in being able to secure his valuable services. Mr. N. N. Khale is the Contractor who has brought the work to a successful conclusion. What this trio does not know about Swimming Pools is not worth knowing. Our thanks are also due to Mr. Murphy, Executive Engineer of the C. & M. Station, who gave us several useful hints and helped us in many ways. These joint efforts have produced a Swimming Pool modern in design and construction.

I think, Sir, you will agree with us that this is one of the finest Swimming Pools in Bangalore, if not in South India, and that we have put the money entrusted to us to good use. We are shortly going to commence the construction of Vocational Class-Rooms for teaching elementary Carpentry and Metal work, with a view to hand-and-eye training and to inculcate the dignity of manual labour. We still need about Rs. 500 to enable us to carry out completely our plans for Vocational Training. We would like you, Sir, to whisper into the ears of the Ladies and Gentlemen present here that if they could spare us a small donation towards our Vocational-Classes, we can assure them that their money will be used just as well as the money expended on the Swimming Pool, if not better. All sums sent to the Principal will be gratefully received and duly acknowledged.

We believe in Vocational Training for our boys. We believe that many of our young men and women must find employment on the land, with its accompanying industries, in future. We have visions of a Baldwin Rural Re-construction Unit being established in the near future on the outskirts of Bangalore in conjunction with this School, if we receive the support of the Public.

And now, Sir, we wish to thank you heartily for your presence here. You have honoured us greatly by being with us on this occasion and we offer you our grateful thanks. It only remains now for you to formally declare the Pfeiffer Swimming Pool open by using this key which I have great [redacted] to you, and asking you to keep as a memento of this happy day for us.

After the formal opening of the Pool the ladies and gentlemen present are invited to inspect the Pool and witness a short programme of aquatic sports.

I am, Dear Sir,

Your most obedient servant,

(SD) C. N. WESTON, PRINCIPAL,

BALDWIN BOYS' HIGH SCHOOL.

BANGALORE,
22nd August 1935

The Pfeiffer Swimming Pool

TO THE HON'BLE
LT.-COL. C. T. C. PLOWDEN, C.I.E.,
RESIDENT IN MYSORE

DEAR SIR,

WE are assembled here this evening to witness the inauguration of the Pfeiffer Swimming Pool. Before asking you to formally declare it open, I would like, Sir, on behalf of the Baldwin Boys' High School, to thank all those who have had a share in the consummation of this beautiful structure and to add a few remarks in general.

I wish Mr. and Mrs. Henry Pfeiffer of New York could have been present on this occasion to see the happy expectant faces of our boys who have been dreaming of this Pool for some time. We thank God and the Oldhams for establishing the friendly contact between the Pfeiffers and the Baldwin Boys' High School. Mr. and Mrs. Pfeiffer paid $5,000 into the funds of this School in 1933 and early this year they sent us $1,000 towards the cost of this Pool. Baldwinians will never forget the debt we owe these dear people.

Mr. and Mrs. Pfeiffer have paid more than half the cost of this Pool. The balance of the funds have been obtained from Parents, Old Boys and Friends of the School. The Fancy Sale held in 1934 yielded over Rs. 1,000. Our grateful thanks are due to all those who have responded to our Appeals. Our most generous donors are Bishop W. F. and Mrs. Oldham. Amongst the Parents Mr. C. Amos has helped most liberally. Mr. Cecil Eagles heads the list of contributors from amongst Old Boys.

Mr. G. T. Bridges is the Engineer who drew up the original plans of the Pool. He also supervised and watched its construction on behalf of the School. Mr. Gardener, of the Railway and General Engineering Company, is the Architect and " Reinforced Concrete Expert " to whose skill we owe a great deal. He has had a vast experience in this type of work and we were indeed fortunate in being able to secure his valuable services. Mr. N. N. Khale is the Contractor who has brought the work to a successful conclusion. What this trio does not know about Swimming Pools is not worth knowing. Our thanks are also due to Mr. Murphy, Executive Engineer of the C. & M. Station, who gave us several useful hints and helped us in many ways. These joint efforts have produced a Swimming Pool modern in design and construction.

I think, Sir, you will agree with us that this is one of the finest Swimming Pools in Bangalore, if not in South India, and that we have put the money entrusted to us to good use. We are shortly going to commence the construction of Vocational Class-Rooms for teaching elementary Carpentry and Metal work, with a view to hand-and-eye training and to inculcate the dignity of manual labour. We still need about Rs. 500 to enable us to carry out completely our plans for Vocational Training. We would like you, Sir, to whisper into the ears of the Ladies and Gentlemen present here that if they could spare us a small donation towards our Vocational-Classes, we can assure them that their money will be used just as well as the money expended on the Swimming Pool, if not better. All sums sent to the Principal will be gratefully received and duly acknowledged.

We believe in Vocational Training for our boys. We believe that many of our young men and women must find employment on the land, with its accompanying industries, in future. We have visions of a Baldwin Rural Re-construction Unit being established in the near future on the outskirts of Bangalore in conjunction with this School, if we receive the support of the Public.

And now, Sir, we wish to thank you heartily for your presence here. You have honoured us greatly by being with us on this occasion and we offer you our grateful thanks. It only remains now for you to formally declare the Pfeiffer Swimming Pool open by using this key which I have great pleasure in presenting to you, and asking you to keep as a memento of this happy day for us.

After the formal opening of the Pool the ladies and gentlemen present are invited to inspect the Pool and witness a short programme of aquatic sports.

I am, Dear Sir,

Your most obedient servant,

(SD.) **C. N. WESTON, PRINCIPAL,**
BALDWIN BOYS' HIGH SCHOOL.

BANGALORE,
22nd August 1935

S N 2

Note.-

On page 13 of the Principal's Report for the year 1934, Mr. Weston has asked the Resident for an assurance of the support of Government in regard to certain improvement schemes.

The two schemes at present under consideration are the provision of a Swimming Bath and the construction of two class rooms for instruction in carpentry, metalwork and commercial subjects. Funds for the Swimming Bath are available. The proceeds of a Sale and Concert recently held by the school are earmarked for the Bath, and the balance has been provided by Mr. and Mrs. Pfeiffer of New York.

Mr. Weston has obtained a promise of a grant of Rs. 2,500/- from the European Schools Improvement Association towards the cost of the new class-rooms, provided that the school can provide an equal amount. It is this sum of Rs. 2,500/- that Mr. Weston wants Government to grant. I proposed the inclusion in the Budget for the current year of certain sums for grants to this school, but the extra provision for this and other items has not, I understand been included. The normal allotment for ' Building and Furniture grants ' to Secondary schools has been reduced from Rs. 9,000/- to Rs. 6,000/-. It is unlikely therefore, that I shall be able to spare from this allotment, so large a sum as Rs. 2,500/- for one school. Mr. Weston is naturally anxious about this as, unless he can raise Rs. 2,500/-, he forfeits a similar amount already provisionally promised to him by the European Schools Improvement Association. We might be able to spare the school Rs. 1,000/- this year and promise a similar amount next year to enable the school to claim at any rate Rs. 2,000/- this year from the Association.

But I thought it better to include a non-committal statement about this in the Speech put up.

SN-3

C. N. WESTON, M.A. M.R.S.T.
PRINCIPAL

No. G. 19.

BUSINESS HOURS : 9-15—10 A.M. 3-45—4-15 P.M.

BALDWIN BOYS' HIGH SCHOOL
BANGALORE

Dated 22nd March 1935.

To,

Lt.Col. C. T. C. Plowden, C.I.E.,
British Resident in Mysore,
The Residency, Bangalore.



Dear Sir,

We were very disappointed that you were not able to preside at our Distribution of Prizes. We know, however, that you were too ill to be present although you were very anxious to be with us. You will be glad to know that the function went off very successfully. Major General Flemming made a very good chairman in your absence.

We have not, Sir, been given anything definite yet about the government grant for our Improvement schemes. All the other grants have been finally sanctioned except the government grant. If we do not get at least Rs.2,500 from the government, we shall automatically lose a grant of Rs.2,500 from the European Schools' Improvement Association of India. Mrs. Henry Pfeiffer of New York has given us Rs.2,500 for the Swimming Bath and the parents and Old Boys have subscribed Rs.2,500 for the Swimming Bath. These two sums must be ear-marked for the Swimming Bath. The European Schools' Association of India has made a grant of Rs.2,500 towards the vocational and other purely educational improvements. The school cannot raise any more money at this juncture. If the government does not give us at least Rs.2,500, we cannot proceed with the Vocational Class rooms and other educational improvements. And so the grant from the European Schools' Association will automatically lapse. We hope, Sir, the government will be able to tell us definitely in the very near future that we can expect at least Rs.2,500 towards our schemes.

We hope your eye trouble is much better and that you will soon be quite well.

I beg to remain, Dear Sir,
Your most obedient servant,

Weston.

S.N. 2

DEPARTMENT.

BRANCH.

File No:

Serial No:

Issued 26/4/35

D 6

Draft

Letter / Memorandum / Telegram

Class for telegrams

Ordinary / Express / Urgent* / Priority / Clear Line†

*Only for Foreign Telegrams.

†Not for Foreign Telegrams.

No. D.2936 R.e.u Dated 26-4-1935

To be issued on

Issued on

1st Reminder

2nd Reminder

3rd Reminder

Heading :

Case or Diary No.

If post copy of telegram required

Date of despatch of above

List of enclosures S.N. 2

(Code word for telegrams.)

To

C.N. Weston Esq., M.A., M.R.S.T.,

Principal, Baldwin Boys' School

Dear Sir,

I am desired to acknowledge the receipt of your letter dated the 22nd March 1935, regarding Govt. grant for Improvement Schemes for your school, and to say that the present state of the Assigned Tract Revenues has made it necessary to postpone consideration of many proposals for new expenditure. and It is not possible Therefore to promise anything more than Rs. 1,000 for your schemes during the current financial year and a similar amount next year. It is hoped that this will enable you to claim at any rate Rs. 2,000 ~~this year~~ from the European Schools' Association.

yours faithfully,

C.G.E. 25/4

F.N.T Secy. to the President.

Copy to the Inspector of Schools with Secy's Compliment slip.

C.G.E. 19/4

S.S.

MG[illegible]-335 (CPS) DOF—(G-1432)—24-4-31—50,000 Pads

S.W.5

EDUCATIONAL DEPARTMENT.

P.w.c I

In future letters, please quote No. 3208/B/2/35 dated and short title*	Rec'd 13/2/35 Reg'd	*Enclosures* 3+1 *Spare copies*	All communications to be addressed to the official address and not by name.

Dated 193

From

OFFICE OF THE RESIDENT IN MYSORE.
BANGALORE.
13 AUG. 1935
Regd No. 7775
File No. 1024/35

F.F.C. Edmonds, Esq., M.A., B.Sc.,

Inspector of Schools, Coorg and Bangalore.

To The Secretary to the Hon'ble the Resident

in Mysore, Bangalore.

Sir,

I have the honour to state that I have received an application from the Correspondent, Baldwin Boys' High School, Bangalore, for a grant towards the construction of vocational class rooms and the improvement of the existing latrines, and for the purchase of Science and other apparatus, the entire cost amounting to Rs. 5,931-6-0. Towards this I recommend the payment of a grant of Rs.2,500/- to enable the school to draw an equal amount from the European Schools Improvement Association; but owing to the reduction made under the head "Building grants to Secondary schools" in my budget for 1935-36, it is not possible to allot such a large grant to any one school this year. I have therefore reserved a sum of Rs.1,500/- for this purpose this year and have promised the Correspondent that I would recommend the sanction of a further grant of Rs.1,000/-, next year, if funds permit. To this the Correspondent agrees. The scheme for ~~for~~ vocational class rooms has, I think, already been brought to the notice of the Hon'ble the Resident. I strongly recommend the application. The scheme should prove most valuable in providing facilities for vocational training, not only incidentally to the ordinary school work, but also, for those boys who have no aptitude for higher studies, as an alternative to the academic course.

S.N.4 (2)
C.P.4

I recommend that under article 52 of the Code of Regulations for European Schools in the Civil and Military Station, Bangalore, a grant amounting to Rs.750/- be sanctioned towards the cost of construction of vocational class rooms and for improving the existing latrines. The balance of Rs.750/- promised for this year is for the purchase of Science and other apparatus and this is being dealt with in a separate reference. Specific sanction for an additional grant of Rs.1000/- towards the cost of the Building Scheme will be sought next year; but a provisional promise, that, subject to the existence of funds, this amount will be paid next year, may kindly be given in order that Mr. Weston may claim the full contribution of the European Schools Improvement Assiciation this year.

* S N.6 (Page 11)

The amount will be met from the allotment under "Account II- Education - B.Secondary - Grants-in-Aid to non-Government Secondary Schools - Building Grants" in the current year's Mysore Assigned Tract budget.

The Plan and Estimate prepared by the Municipal Executive Engineer and the application for a Building grant are also enclosed together with a copy of the Correspondent's letter dated 2.8.1935 requesting that early orders may kindly be passed on this application.

I have the honour to be,

Sir,

Your most obedient servant,

Inspector of Schools,

Coorg and Bangalore.

RM/12.8.

Edl. C-I.10—156—26-5-31.

Application for Building Grant towards the cost of (1) Vocational Class Rooms (2) Swimming Bath (3) Alterations to Flush System.
~~School at~~ in Baldwin Boys' School **in the district of** Bangalore.

1. Number and date of the proceedings or memorandum recognizing the school under the Code of Regulations for European Schools.

No. 6898/9-12-1901.

2. Brief history of the institution from the date of its establishment to the date of application tracing its growth and development and furnishing among other things an accurate account of its financial condition.

Please see recent Inspector's Reports.

NOTE.—(1) This need not be given if a reference to a history previously given can be furnished.

3. Governing Body .. .. .. The Board of Governors.

4. Management .. .. .. Bishop B. T. Badley - Rev. C. L. Camp - Rev. W. J. McLaughlin - C. R. Weston.

5. The strength of the different standards as it stood on the 31st March of every year for five years preceding the year in which the application is submitted.

——	193~~1~~/	193~~2~~	193~~3~~	193~~4~~	193~~5~~	Number of pupils in each standard on the date of the application.	Number of pupils that can be accommodated in each class room.
Standard IX	13	14	10	14	13	13	25
„ VIII	12	9	11	12	14	14	25
„ VII	10	11	11	16	16	16	25
„ VI	15	13	15	13	14	14	25
„ V	17	16	18	15	21	21	25
„ IV	16	22	18	20	21	21	25
„ III	18	16	11	14	16	16	25
„ II	13	13	15	10	12	12	25
„ I	-	-	-	-	-	-	-
Kindergarten Standard, Upper.							
„ „ Lower.							

NOTE.—If there be any striking variations in the strength as shown above, such variations should be accounted for.

(1) Character of, necessity for, and purpose of, the proposed work.

(2) Is a site p'an and sketch plans of the proposed building attached ?

(3) Does it show

(*a*) the relation of the proposed building or extension to the existing buildings?

(*b*) any alteration in existing buildings necessitated by it ?

(*c*) the purpose to which the existing buildings are now put ?

(*d*) the purpose to which they will be put when the new building or extension is complete ?

NOTE.—(i) Any notes that cannot be conveniently inserted in the plan may be given under each of the above headings.

(ii) The rooms of the sketch plans should be lettered or numbered and a key supplied.

(4) Probable cost of the proposed work.

(5) Whether the management has the necessary funds to complete the work in the event of the application being favourably considered.

(6) Whether the governing body is registered under any act of the Local or Imperial Government, if so state the act and number and date of certificate.

(7) If the aid sought for is towards the cost of site, declaration that it is the cheapest suitable site.

(8) Declaration that the governing body is prepared to execute the prescribed deed if required by the Director to do so.

(9) If the property is not owned by the governing body, declaration that the owner or his or her legal representative will execute the deed or will be made a party to the deed.

(10) The name and address in full of the person who holds power-of-attorney on behalf of the governing body to execute the prescribed deed.

(11) Name, designation and qualification of the person by whom detailed plans and estimates and specifications will be prepared.

(12) Whether the title to the property is clear and in order and by whom the title-deeds were examined.

(13) The latest date on which the management wishes to (i) begin the work and (ii) complete the work.

(14) Is the declaration with regard to encumbrance, alienation and the conditions of recognition and aid attached.

(15) Amount of building grants drawn by the institution in previous years with the number and date of the sanction and the purposes for which given. Particulars should be given for 40 years.

(16) If the aid sought is towards the construction of a boarding house, declaration that the boarding house will be managed according to rules approved by the Department.

2 (1) Vocational classes (2) Swimming Bath (3) Alterations to Flush System

Yes — two plans

Yes

Nil

Staff quarters & pavilion

As before

Vocational Rooms Rs. 3100
Swimming Bath 4000.
Alterations to latrine 425.
Supervision, plans incidentals 475
Total Rs. 8000.

Yes.

No.

No expenditure on site.

Yes.

The Board of Trustees will execute the deed.

(1) Rev. C. L. Camp M.E. Mission Kolar.
(2) C.N. Weston, Bangalore
G.T. Bridges, Executive Engineer (Retd.) and Executive Engineer, Bangalore.

Yes; The Finance Committee of our Conference.

(1) 1st July 1935.
(2) 30th September 1935.

No encumberance; yes.

5 years list attached.

Not on hostel.

№18

BALDWIN BOYS' HIGH SCHOOL

The Annual Expenditure of Up-keep (Repairs to Building.

For five Years.	School.			Boarding			Total			Remarks.
	Rs.	As	p	Rs.	As	p	Rs.	As	p	
1930 - 1931							723	4	7	Met by fees
1931 - 1932	597	0	0	969	4	9	1566	4	9	Government
1932 - 1933	385	11	9	523	9	10	909	5	7	
1933 - 1934	432	13	3	537	15	9	970	13	3	Grant, and
1934 - 1935	726	11	0	1074	7	1	1801	2	1	other Sources

Inspector
29/4/35

(12)

No 15

Grants sanctioned under Article 50 of the Code of Regulations for European Schools and Rule 43 of the Grant-in-Aid Code for Indian Schools to be entered-

S.No.	Particulars of buildings or lands purchased or repaired.	Date of Completion of the work.	Actual Cost.	No. & date of the Hon'ble the Resident's proceedings sanctioning the grants or order of the Inspector of Schools.	Amount of grant sanctioned.	Date on which grants were drawn.	Inspector's No. and date of the order authorising the payment.	REMARKS. (Indicating the purpose for which purchased, constructed etc.)
1	2	3	4	5	6	7	8	9
			Rs. As p		Rs. As p			
1.	Towards the purchase of lands, erection and enlargement of buildings.	30 - 1- 32 Date of completion certificate from the Engineer.	58280 2 4	5766/ dated 21-7-1931	5127 0 0 4873 0 0 5000 0 0 2000 0 0	26-11-30 25- 2-31 31- 3-31 1- 2-32	3883/24 date 15-11-30. 584/1/24 17-2-31 1079/1/24 30-3-31 294/1/24 1-2-32.	For use of play-ground, Hospital etc.

Preston
29/4/35

ESTIMATE FOR RE-CONSTRUCTING THE LATRINE IN

BALDWIN BOYS' HIGH SCHOOL.

			Rs.	As.	p.
To dismantling existing seats and removing debris			9	0	0
dismantling stoneware, pipes and fittings			4	0	0
dismantling G. I. piping			2	0	0
Providing and fixing white glazed English closets complete with trap. 6 Nos.	@	25/-	150	0	0
Constructing inspection chambers in brick and mortar, cement plastered, including C.I. frame and cover.					
1 No. Size 18 x 18	@	20/-	20	0	0
1 No. Size 18 x 12	@	15/-	15	0	0
Providing and laying & jointing 4" dia. stoneware pipes including earthwork excavation etc., 24 rft ...	@	/12/-	18	0	0
Connection to manhole			1	0	0
Boring through foundation and redoing			3	0	0
Fixing wooden rests for seats 6 prs.	@	1/-	6	0	0
Brick and lime masonry for closets 2 x 1½ x 1½ 6 Nos. 27 cft.			10	2	0
Cement plastering 31.5 sq.ft.			3	0	0

Water Supply:

Providing and fixing 1 No. ¾" wheel valve			2	4	0
Providing and fixing automatic flushing tank of 45 gallons complete with fittings			55	0	0
Providing cutting threading laying & jointing: 30 fft ½"dia.piping ...	@	1/-	30	0	0
4 Nos. 2 x 1½ tees	@	1/-	4	0	0
1 No. 2 x 2 tee	@	1/4	1	4	0
2 Nos. 2 x 1½ rd. elbow	@	1/4	2	8	0
6 rft 1½" dia. piping	@	/12/-	4	8	0
Boring through foundation & redoing			1	8	0
Extending Asbestos roofing to existing latrine 16 x 3 - 48	@	/10/-	38	0	0
Dismantling and redoing cornice 16 rft	@	/8/-	8	0	0
Total Cost Rs.			403	2	0

E.&.O.E.

Inspector.
29/4/35

(17) The treasury at which the grant, if sanctioned, is to be payable. The Hon'ble the Resident in Mysore's Treasury, Bangalore.

(18) The annual expenditure incurred in the upkeep of the institution and how it is met from—

(1) Fees.
(2) Government grant.
(3) Other sources.
(4) Manager's funds.

(Particulars for five years to be furnished.) List attached

Inspecting Officer's remarks about accommodation from his inspection reports for the two previous years.

1932 - 1933 = Adequate.
1933 - 1934 = Adequate.

Director's review of such remark.

Declaration with regard to encumbrance, alienation and the condition of recognition and aid—"On behalf of the governing body of school, I hereby declare that the property is unencumbered and that it will not be alienated or encumbered without the consent of Government within forty years and that the conditions of recognition and aid laid down in the Code of Regulations for European Schools are being and will continue to be fully observed, excepting those rules from which the institution has been specially exempted by the Director's Proceedings No. , dated ; and that I am prepared to subject the institution, together with its current, endowment and trust accounts, its establishment, time-table and registers to inspection, and to furnish such returns as may be required by the department and that I shall abide by the provisions of Article 150 of the Code of Regulations for European Schools in the event of the building ceasing to be used prior to the lapse of forty years after the date of payment of grant for educational purposes approved by Government."

STATION Bangalore
Date 27th April 1935.

Weston
Correspondent.
BALDWIN BOYS' HIGH SCHOOL,
BANGALORE.

Letter No.G.36, dated the 2nd August,1935, from the Correspondent, Baldwin Boys' High School, Bangalore, to the Inspector of Schools, Coorg and Bangalore.

I have the honour to submit to you the following facts regarding our Vocational Class Rooms:-
(1) Report; (2) Estimates and (3) Plans.

All these have been prepared and signed by the Executive Engineer, Civil and Military Station,Bangalore.

I regret to say that the Municipal Engineer has sent only one copy of each to us. If you need any further copies please refer to the Municipal Engineer.

As we wish to start the construction of these Class rooms as soon as possible, will you, Sir, kindly push the matter through at your earliest convenience. I have to have all these Bills completed and presented to the European Schools Association in Calcutta before the 15th November 1935. The works have to be certified for and the money drawn before the end of this calendar year. Under these circumstances we shall be glad to have sanction to proceed as early as possible.

(Copy)

H Rammos

Inspector of Schools,
Coorg and Bangalore.

5—20,000—26—9—1934.

Margin for binding not to be written on.

Notes—*Continued.*

REPORT TO ACCOMPANY THE ESTIMATES.

Provision is made in the estimate for constructing Vocational class rooms, ~~latrine~~ and improving the existing latrine in the compound of Baldwin Boys High School on Hosur road, as per accompanying plans.

The Vocational class rooms consisting of two halls with two small rooms between them and a verandah 10 feet wide in front to the full length.

Foundations will be of stone in clay masonry the exposed joints pointed with cement.

Superstructure will be of brick in clay masonry except the sides of doors, windows and tops of walls which will be of brick in lime masonry, lime plastered on both sides.

Frames of doors, windows and ventilators will be of teak wood with 1¼" thick panelled shutters for doors 1" thick half panelled and half glazed shutters for windows and 1" thick fully glazed shutters for ventilators complete with all requisite fittings and the surface painted with 2 coats of approved ready mixed grey silicate paint.

Roofing will be of stone slabs complete with surki concrete, two courses of flat tiles etc., carried on rolled steel beams of section provided in the estimate.

Necessary cornices parapet walls etc., will be provided for the roof.

Flooring will be of 1" thick Cadappa slabs laid over a bed of 6" stone in lime concrete the

the joints pointed with cement.

The verandah will be enclosed with expanded metal of 1½" mesh fixed to teak wood frames.

G.I. rain down pipes of 4" in diameter will be provided alround the building to drain off rain water.

Doors, windows and ventilators will be provided with 2" thick reinforced cement concrete slabs for sun-shades, resting over brackets of the same material.

-:-

The existing seats stone-ware and G.I. pipes and fittings will be completely dismantled and white glazed English closets with traps for seats will be fixed and the washings connected to the existing main, through 4" in diameter stone-ware pipe drains.

Fixing a storage tank measuring 3' x 3' x 3' of 1½" thick cement plaster reinforced with hessian cloth over the existing masonry supports for flushing purposes.

The existing roof will be extended over the seats up the screen wall with Asbestos - corrugated sheets.

Necessary inspection chambers and water connections to the storage tank will be fixed and 2" G.I. pipe ventilating shaft will be fixed at the head of the sewer.

PSG. 27/7

EXECUTIVE ENGINEER

Notes—*Continued.*

Margin for binding not to be written on.

L.F. Form No. 70 (Thick)

Estimate—Detailed Measurement Sheet.

15

District..... Taluk..... Taluk Board.....

Name of Work..... Constructing Regional Chemistry Lab for

Main-head..... Composed of Soil Mechanics Lab

Sub-head..... School or Hostel

Estimate No..... 2 193

Amount of Estimate..... Rs. 3554/-

Hoe & Co., Madras.—30-1-1935.

Details of Work.	Number.	Measurement in feet. L.	B.	D.	Area or Contents.	Total quantity of each description of work.
1. Earthwork in [illegible]						
[illegible]	2	[illegible]	[illegible]	[illegible]	[illegible]	
[illegible]	2	[illegible]	[illegible]	[illegible]	[illegible]	
[illegible]	1	[illegible]	[illegible]	[illegible]	[illegible]	
[illegible]	1	[illegible]	[illegible]	[illegible]	24	
[illegible]	2	8 5/6	2½	2½	100	
Steps - above	5	4½	2	½	23	
	Total c/f					1465
2. Stone in cl[illegible] foundation & basement						
[illegible]	2	41½	2½	½	103	
[illegible]	2	41½	2	½	83	
[illegible]	2	40 2/3	1½	¾	121	
End [illegible]	1	[illegible]	2½	[illegible]	[illegible]	
do	1	14	2	½	28	
do	4	14 5/6	1½	¾	301	
Partition [illegible]	1	5 5/6	2½	½	[illegible]	
do	1	6½	2	½	[illegible]	
Verandah [illegible]	1	6 5/6	1½	3	30	
Verandah Compd. walls	1	41 2/3	2½	½	52	
do	1	41	2	½	41	
Back [illegible]	1	[illegible]	½	[illegible]	[illegible]	
End walls of Verandah	2	5 5/8	2½	½	11	
[illegible]	2	[illegible]	2	½	[illegible]	
Plinth [illegible]	2	7 1/3	½	3	57	
Steps	5	4½	2+1/2	1	33	
	Total c/f				498/20	
Deduct for sills of doors	8	5	1½	⅓		
	Balance c/f					1478

Estimate—Detailed Measurement Sheet—*Continued.*

Details of Work.	Number.	Measurement in feet. L.	B.	D.	Area or Contents.	Total quantity of each description of work.
3. Earth [illegible]						
Carpenter's room	1	12 5/8	10 3/8	1/4	100	
Drawing room	1	11 5/8	11 3/8	1/4	100	
Store room	2	6 5/8	6 3/8	1/4	77	
Verandah	1	7 5/8	2 3/8	1/4	155	
Total A						1615
4. Substructure — Burnt Brick in mortar						
Steps in front	3	12	1'3	1 - 0	27	
Plinth	4	12	1'3	1 - 0	48	
Verandah	1	12	1'3	1 - 0	12	
Verandah curtain	2	11/6	1/2	3 1/2	20	
Total C/f					2217	
Deduction - Doors - 4'x7'	5	4	1/8	2	15	
" 3'x7'	3	3	1'3	7	71	
Windows - Brick	7	3	1'3	1 1/2	16	
Ventilator	1	3	1'3	1'1/2	1	
Brick in lime mortar, [illegible]						
[illegible]	[illegible]	3/4	[illegible]	[illegible]	[illegible]	
3'7	3x2	3/4	1'3	7	[illegible]	
[illegible]	[illegible]	3/4	[illegible]	4 1/2	53	
do — ventilator	1	3/6	1'2	1/2	30	
Bottom of do —	12	4 1/2	1'3	3/4	46	
Lintels of doors 4'x7'	5	5 1/2	1/8	1/2	15	
do — 3'7	3	4 1/2	1/8	1/2	8	
Windows	7	4 1/2	1/8	1/2	18	
Ventilators	1	3/4	1/8	1/2	20	
Sills of windows	7	4 1/2	1/8	1/3	12	
Total C/f			C.O.		10	

To be filled in by the Local Board's Office.

Date of receipt in Board's Office.....193 .

Sanctioned for Rs.....in Board's

Proceedings No.....dated.....193 .

Overseer,.....Taluk.

.....

Dated.....193 . *President.....Board.* *L. F. Engineer.*

L. F. Form No. 70. (Thick).

Estimate—Detailed Measurement Sheet—*Continued.*

Hos... Co., Madras.—25-4-84

Details of Work.	Number.	Measurement in feet. L.	B.	D.	Area or Contents.	Total quantity of each description of work.
Std Deduct 0.7						102
Balance						1575
a. Rubble lime masonry.						
Plinth	5	5	1½	1	37	
Walls in cm. thick	1	5	1½	1	223	
Portico of verandah	2	10	1½	¾	45	
End faces of walls	4	15	1½	¾	51	
Partition walls of	1	7	12	¾	4	
Inside of walls	1	46	½	¾	17	
Masonry over pillars of Verandah	1	22	½	¾	14	
Total Cft						430
b. Work in finishing (masonry in superstructure)						
Cornice	1	30	2	1	Item	
Coping	1	30	2	1	Item	
Parapet wall	1	30	1½	1	Item	
Pilasters for cornice	7	1½	2	1	105	
Pilasters for Parapet	7	1½	1½	1	Item	
Total Cft						38·17
c. Stone slabs 2" thick set in lime						
Outside over doors (3×7)	5	3½	1		28	
do 3×7	3	4½	1		14	
Windows	7	4½	1		32	
Ventilators	12	1½	1		18	
Over Pillars for Verandah	7	1	1		7	
Ends of E. W. Walls	4×5	1½	1		17	
Total						117
d. Stone slabs 2" thick -						
Sills of Doors	5	5	1½		60	
do Windows	7	4½	1		32	
			6.0		92	

Estimate—Detailed Measurement Sheet—*Continued.*

Details of Work.	Number.	Measurement in feet. L.	B.	D.	Area or Contents	Total quantity of each description of work.
Flush of Verandah floor	1	41	1½		62	
						62
9. Teakwood 1½" thick framed shutters complete						
Casuarina	2	3½	6½		118	
do	1	3½	3½		11	
						11,
10. Teakwood 1" thick framed & panelled shutters complete						
11- Y.W. Ranger shutters 1" thick						
Partitions	12	2⅞				
12 Iron bars						
⅝" R.B. bars in window openings	24	2½			41	
do Fanlights	12	2½			65	
						215
13. Teakwood framed panelled doors complete						
Casuarina & Ranging room	3	17	(10"×5")		638	
Verandah	1	12	(7"×4")		266	
Non Verandah Cattle	1	40	(do)		240	
						3130
						28.
14. Reeling posts						
Main Cattle	1	39	16		936	
Verandah	1	57	11		957	
						1893

Carried over

L. F. Form No. 70. (Thick).

Estimate—Detailed Measurement Sheet—*Continued.*

Hoe & Co., Madras.—25-4-84

(17)

Details of Work.	Number.	Measurement in feet. L.	B.	D.	Area or Contents.	Total quantity of each description of work.
15- Brick in lime cornice 6" in projection						
Outside chunam - N.13 -	1	119½	-	-	120.	
Verandah 3 sides -	1	64¾	-	-	65-	
Dope of pillars -	7	8½	-	-	60.	
Total R/f						245-
16. 3" Cornice below roof inside.						
Verandah.	1	96½	-	-	97.	
Rooms -	1	64+54	-	-	118	
Projections -	2	25½	-	-	97-	
Total R/f						272.
17- Brick in lime plain parapet 2' high						
Complete - N.13. Chunam	1	115½	-	-	116.	
Between col. 2 sides	1	6½			6	
Between ver-pillars	1	24⅝	-	-	25-	
Total R/f						204.
18 Plastering with 1" thick cement-finish						
Sloping chunam 3" thick concrete bed.						
& cement pointing joints -						
Carpentry room	1	17	15-	-	255-	
Drawing	1	12	15-	-	180.	
Foyer -	2	7	7⅛	-	100.	
Verandah	1	38½	10		385	
Total R/f						918
19- Cement pointing Verandah.						
Chunam	1	130½		1¾	244	244.
20- Chunam plastering ½" thick.						
Inside - Carpentry room	1	64	-	13½	864.	
Drawing -	1	54	-	13½	729.	1593.

Estimate—Detailed Measurement Sheet—*Continued.*

Details of Work.	Number.	Measurement in feet. L.	B.	D.	Area or Contents	Total quantity of each description of work.
				8.7	1575.	
Slopes	2	28¼	-	13½	763.	
Verandah 3 sides.	1	58¼	-	9	524.	
Pillars abroad.	5	4½	-	8	180.	
Jambs of doors.	5	18	5/6	-	75.	
do —	3	17	5/6	-	43.	
do windows.	1	15	5/6	-	38.	
do — Ventilators	12	7	5/6	-	90	
Total sft					3356	
Deduct. doors.	2×5	4	-	7	280	
do —	1×3	3	-	7	63.	
windows.	1	3	-	4½	95.	
Ventilators	12	3	-	1½	54.	
Total deductions					492.	
Balance inside plastering					2864.	
Outside N.B. Abroad 3 sides	1	115½	-	13½	1560	
Front above Ver. Roof	1	40½	-	4	162	
Verandah ends	2	11⅝	-	7	200.	
Faces of end walls	2	1⅛	-	7	20.	
Total sft					1942.	
Deduct. doors.	3	3	-	7	63.	
windows.	1	3	-	4½	95.	
Ventilators	12	3	-	1½	54.	
Total deductions					212	
Balance outside plastering					1730.	
Cf. Total plastering sft						45
21- Approved ready mixed grey colour						
painting 2 coats - Doors	2¼×5	4	-	7	315	
	2¼×3	3	-	7	142	
½ panelled ½ glazed windows	2×1	3	-	4½	189.	
Glazed sashes.	1⅛×12	3	-	1½	68	
Total sft					714.	

(18

Estimate—Detailed Measurement Sheet—*Continued.*

Details of Work.	Number.	Measurement in feet. L.	B.	D.	Area or Contents.	Total quantity of each description of work.
22. White washing 2 coats on internal plastering					7864	2564.
23. Colour washing 2 coats (Grey). on external plastering sft					1730	1730
24. Cement concrete kerbs 3" thick. for Sunshade - 3 sides 1x2					6.	
windows	1x2				14	
Walls -	12x2				24	
Total						44.
25. Re. cement concrete Sloping 3" thick for Sunshade - 3 sides 2		5			10.	
windows	1	5	2		10.	
Ventilator.	12	5	2		120.	
Total sft						220.
26 Dressing one line. Plinth plinth edges	1	411	1/3		10	
Sft - columns.	1	411	1/2		20.	
Slopes (Inclined rise)	5	4 1/2	2		45	
sides -	4 1/2	1	1/2		10.	
Total sft						112.
27 - G.I. Rain down pipes 4"	3	15			45.	
	2	5			15.	
	3	2			6.	
Total Rft.						66.
28 Painting 2 coats of enamel paint over horns at sides of concrete - 1 Nos.					1	1.

Estimate—Detailed Measurement Sheet—*Continued.*

Details of Work.	Number.	Measurement in feet. L.	B.	D.	Area or Contents.	Total quantity of each description of work.
X-P-M- Sheets						
29. D.I. bracket frames 2 sheets.						
Vertical's -	4×3	6	4	6	3·00	
Horizontals	3×2	6	4	6	1·50	
do -	3×2	6 2/3	4	6	1·55	
Corner frames	2	-	2/3	1/4	3·67	
Dofs of room	2	1	4 3	4	1·17	
Total c/f						10·92.
30. D. Mon's balconies.						
Shutter frame balcony	2	70 1/3	4	1/6	3·37	
Central Style of above	2×2	6 5/12	1/4	1/6	1·09	
Knee rails -	2	3 2/12	3/4	1/6	0·90	
Total c/f						5·38.
31. Expanded metal 1½" mesh.						
Verandah:	2	6	-	6	1/2	
do -	2	6/3	-	6	76	
Screens	2	5 2/12	-	6 2/12	47	
Dofs of doors	2	4	-	1	8	
Total c/f						203.
32. 4" Iron bath hinges with -						
Screws -	6×2				1/2	1/2
33. 6" Iron bolts fixed complete	3×2				6.	6.
34. Hasps & staples	2				2	2
35. Oil'd ready mixed paint (grey) 2 coats						
for X-12 sh.	2	6	-	6	72	
do	2	6 5/12	-	6	76	
Dressed fofs	2	4	-	8	64	
Total c/f						212.

P.W.D. V.-13—3,000—14-2-34 (6).

ESTIMATE FORM—Abstract.

E. No. 31—Inner.

Item number. (1)	Quantity. (2)	Description of work. (3)	Rate. (4)	Per (5)	Amount. (6)	Total. (7)
			RS.		RS.	RS.
1.	1465.	Earthwork excavatin.	9/-	100 c/f	13.	
2.	1478	Stone in clay foundt bast.	28/8/-	100 c/f	421	
3.	1089	Earth filling in bast.	5/-	100 c/f	5	
4.	1595.	Brick in clay superstructure	24/4/-	100 c/f	387.	
5.	430	— do — lime — do —	35/-	do	151.	
6.	38·17	Teak wood wrought, framed fixed-	6/12/-	c/f	258	
7.	197.	Stone Slabs 6" thick sel in lime	31/4/-	100 s/f	62	
8.	154.	Stone slabs 4" thick -	22/8/-	do	35-	
9.	169.	D.W. 1¼" thick panelled shutters	1/4/-	s/f	211.	
10.	71.	D.W. half panelled ½ glazed 1" thick shutter	1/1/-	s/f	75.	
11.	37.	D.W. glazed shutters 1" thick -	1/-	s/f	37.	
12.	265 lb.	Iron work	14/-	cwt	33	
13.	28 cwt	R.S. Beams complete.	12/8/-	cwt	350	
14.	10/3	Roofing with Stone Slabs.	50/-	Sq.	513/-	
15.	245	Brick in lime Cornice 6" in pro-	0/6/-	R/f	9 2	
16	2/2	— do — 3" in pro-	0/3/-	R/f	51	
17.	204	Plain parapet 2' high.	1/-	R/f	204	
18	918.	1" thick C. floor on lime concrete 6"	25/8/-	Sq.	234.	
19.	244.	Cement pointing bast.	2/4/-	Sq.	5-	
20	1594	Chunam plastering ½" thick	3/-	do	138	
21.	714.	Appd - ready mixed oily silicate paint 2 coats	6/-	do	43	
22	286	White washing 2 coats -	0/5/-	do	9.	
23	1730.	Colour washing 2 coats (Grey)	0/6/-	do	6-	
			6.0		3357	

ESTIMATE FORM—Abstract.

Item number. (1)	Quantity. (2)	Description of work. (3)	Rate. (4)	Per (5)	Amount. (6)	Total. (7)
			Rs.		Rs.	Rs.
				B.F.	3357	
24.	44.	Cc. Con. Brackets.	1/-	each	44.	
25.	220.	Cc. Con. slabs (Reinforced) 2" thick	2/4/-	S/C	55.	
26.	112	Dressing one line.	0/2/-	S/C	14.	
27.	66.	C.I. Rain down pipes.	1/-	S/C	22.	
28.	1Cc.	Painting mortar & Cc. 2 coats	2/-	C.S.	2.	
29.	10.92	2 W. Wrought-framed & fixed-	6/12/-	C/C	74.	
30.	5.38	2 W. Planking.	7/8/-	C/C	40.	
31.	2.03	Expanded metal 1½".	2/4/c	S/-	57.	
32.	12.	Batt hinges- 4".	0/6/-	Each	5".	
33.	6.	6" Tower bolts.	7½/-	do-	2.	
34.	2.	Hasps & staples.	0/12/-	do	2.	
35.	212.	Cfpd. ready mixed grey silicate paint 2 coats	6/-	Sq.	13.	
				Total Rs.	3687.	
		Deduct 15% supn. anticipated			553.	
				Balance	3134.	
		5% Contingencies			157.	
					3291.	
		add 8% Supervision charges			263.	
		Grand Total Rs			3554.	

Approximate Estimate
Asst. Engineer. 7.35

Exd. Engr.


PLAN OF THE PROPOSED VOCATIONAL CLASS ROOMS
FOR BALDWIN BOYS HIGH SCHOOL.
SCALE 8 TO 1'
FRONT
ELEVATION.

L.F. Form No. 70 (Thick)

(21

Estimate—Detailed Measurement Sheet.

District..... Taluk..... Taluk Board.....

Name of Work... Improving the Latrine in the compound of L

Main-head... Bellary Dist. Board

Sub-head... On Roads

Estimate No.....199

Amount of Estimate. Rs 375/-

Hoe & Co., Madras.—30-1-1935.

Details of Work.	Number.	Measurement in feet. L.	B.	D.	Area or Contents.	Total quantity of each description of work.
1. Demolishing existing [illegible]	1				1	1
2. Demolishing [illegible]	1				1	1
3. Filling [illegible]	1		1 Ft.		1	1
4. Providing & fixing [illegible]	6				6	6
5. Providing wood [illegible]	1	10'	4"	4½"	Rmo	100
6. Providing Asbestos Cement [illegible]	3	(15"	24")		3	3
7. [illegible]	1	16½			17	17
8. [illegible]	6				6	6
9. Providing [illegible]	6				6	6
10. Cement Plastering [illegible]	1	15'	8'		30	30
11. Brick in lime masonry for [illegible]	6				6	6

Estimate—Detailed Measurement Sheet—*Continued.*

Details of Work.	Number.	Measurement in feet. L.	B.	D.	Area or Contents.	Total quantity of each description of work.
11a.						
12.						
13.						
14.						

L. F. Form No. 70. (Thick).

Estimate—Detailed Measurement Sheet—*Continued.*

Details of Work.	Number.	Measurement in feet. L.	B.	D.	Area or Contents.	Total quantity of each description of work.
20-A 1" G.I. Pipes - inlet to tank	1	12	-	-	12	12
25-26. 1¼" (outlet) G.I. Pipe for scale	1	8	-	-	8	
	1	17	-	-	17	
Total 1¼						25
24. 1¼" G.I. Tees	5	-	-	-	5	5
22. 1¼" G.I. Bends	2	-	-	-	2	2
23. 1¼" G.I. Elbows - Bend for valve	1	-	-	-	1	1
24. 1¼" Iron flanges	2	-	-	-	2	2
25. 1¼" check nuts	1	-	-	-	1	1
26. 1¼" Unions	3	-	-	-	3	3
27. 1" Nipples at ball valve	1	-	-	-	1	1
28. 1" Collar	1	-	-	-	1	1
29. 1¼" Stop cock (Iron)	1	-	-	-	1	1
30. Union for 1" pipe	1	-	-	-	1	1
31. Fixing pipes -	1	37	-	-	37	37
32. Red box cocks	1	-	-	-	1	1
33. 4" S.W. Gully trap	1	-	-	-	1	1

P.W.D. V-13—3,000—14-2-34 (6).

(23)

E. No. 31—Inner.

ESTIMATE FORM—Abstract.

Item number. (1)	Quantity. (2)	Description of work. (3)	Rate. (4)	Per (5)	Amount. (6)	Total. (7)
			RS.		RS.	RS.
1.	6.	Dismantling existing seats etc-	/8/-	LSE	3	
2.	1doz	Listg. S. urinals etc	3/-	LS.	3	
3.	1 "	Listg. G.I. pipes etc	2/-	LS	2.	
4.	6-	Providing fixing white glazed English closets complete.	20/-	Each	120	
5.	100.	Wooden seats complete	7/8/-	c/c	8	
6.	3.	Deep Dno- chambers complete	15/-	Each	45.	
7.	17-	4" S.W. Pipes Bends complete-	2/5/3	R/c	9.	
8.	6-	4" S.W. Bends-	1/4/-	each	8.	
9.	6.	Boring holes etc complete	0/8/-	LS-	3.	
10.	30.	Sqc. plastering 1/2" Thick	1/8/-	Sqr	2	
11.	6.	Brick in lime masonry for seats	2/-	LSE	12.	
11a	1-	2" G.I. Vent Shaft	15/-	each	15	
12.	65	Cement- asbestos roofing-	2/8/-	S/H	34.	
13-	1doz	Listg coping of compd. walls etc	3/-	LS.	3-	
14.	1.	Sqc. plaster Storage tank 3'x3'x3'	10/-	Each	10.	
15.	62 lbs	Iron cover (1/8" Thick Station)	14/-	each	8	
16.	6.	3m. S. 3m. Rails-	1/4/-	R/c	8-	
17.	1doz	Lifting & fixing rails etc-	3/-	LS.	3	
18	1.	1" Ball valve.	2/5/-	each	3.	
19.	3.	1" wheel valve-	1/9/-	each	5	
20	2	1" G.I. Bends-	9/6/8	dr	1.	
20 A	12.	1" G.I. Pipes-	0/3/3	R/c	2	
20 B	25.	1/4" —do—	0/4/6	dr	7.	
				Total Co.	314.	

ESTIMATE FORM—Abstract.

Item number. (1)	Quantity. (2)	Description of work. (3)	Rate. (4)	Per (5)	Amount. (6)	Total. (7)
			RS.		RS.	RS.
				B. F.	34-	
21.	5.	1¼"-G.I. Tees.	0/4/-	each	1-	
22	2	1¼"- Bends-	0/8/-	do	1.	
23	1.	1¼"- Elbow.	0/4/-	do	-	
24	2	1¼" Flanges-	0/4/6	do	1	
25.	1.	1¼"- Check nuts	0/2/-	do	-	
26.	3	1¼"- unions.	0/5/6	do	2	
27	1.	1"- nipple-	0/2/3	do	-	
28	1.	1"- Collar.	0/2/3	do	-	
29.	1.	1¼"- G.m. stop cock.	3/-	do	2	
30	1.	1"- Union-	0/8/-	do	1	
31	37.	Fixing pipes.	2/14/-	R/-	1	
32	1.	Road box with cover.	3/-	each	3	
33.	1.	4" S.W. Gully trap.	3/12/-		4	
			Total Rs.		330	
			5% Contingencies-		17.	
			Total		347.	
			add 5% Supervision charges.		28.	
			G. Total Rs.		375/-	

Approximate Cost
Est. Draftsman 7.35.

Exd. Engineer

IMPROVING THE EXISTING LATRINE IN BALDWIN BOY'S HIGH SCHOOL

SCALE 4' TO 1".



REFERENCE.

—— DENOTES EXISTING PIPE SEWER.
— — " PROPOSED 4" S.W. PIPE LINE
E.C. " " ENGLISH CLOSET -
I.C. " " INS. CHAMBER.
V.S. " " VENT. SHAFT -
G.T. - " " GULLY TRAP -

SECTION ON A.B.



M.I.M. & C.E
EXE. ENGINEER.

Res. Mysore 33.

No. 1024-35 / R.O. II

Dated 29. 9. 1935.

FROM

THE SECRETARY TO THE HON'BLE THE RESIDENT IN MYSORE.

To

THE INSPECTOR OF SCHOOLS,
COORG AND BANGALORE.

Reference :—His letter No. 3208/B/2/35 dated 12th Aug: 1935

Subject :—

Grant to Baldwin Boys' High School for the construction of vocational class rooms and the improvement of the existing latrines.

Under Article/~~Rule~~ 52 of the Code of Regulations for European/~~Grant-in-Aid Code for Indian~~ Schools in the Civil and Military Station of/Bangalore, the Hon'ble the Resident is pleased to sanction a grant of Rs. 750 (rupees Seven hundred and fifty only) during the current ~~or~~ ~~of the actual cost, whichever is less, for~~ year towards the cost of constructing vocational class rooms and improving the existing latrines in the Baldwin Boys' High School, Bangalore

2. The expenditure should be met from the allotment in the Mysore Assigned Tract Budget under the head "Account II—Education. -B. Secondary-Grants-in-Aid to non-Govt. Secondary Schools-Building and furniture grants to Secondary Schools"

2 A further sum of Rs. 1,000 towards the building scheme of the School will be paid next year provided funds are available.

~~Secretary to the Resident.~~

Copy to the Accountant General, Madras.

Secy: to the Resident

20.9.35

T.N.T

1186—9-8-1935—1,000—RPB

No. 653/B/2/35

Office of the Inspector of Schools,
Coorg & Bangalore,
Bangalore, Dated 20 : : 1936

Memorandum.

Read:- Voucher for Rs. 3401/- submitted by the correspondent and a completion certificate from the Municipal Executive Engineer.
Also Memorandum No. F. 1024-35/R.O.II, dated 29-8-1935 sanctioning a grant of Rs. 750/-.

Under article 52 of the Code of Regulations for European schools, ~~xxx~~ in the Civil and Military Station of Bangalore, the Inspector of Schools sanctions and authorises payment of Rupees (750/-) Seven hundred and fifty only towards the cost of constructing vocational class rooms and impreving the existing latrines in the Baldwin Boys' High school, Bangalore, the actual cost according to the voucher produced being Rs. 3401/-.

The amount will be debited to the head " 31. Education- B. Secondary - Direct grants to non-Government Secondary schools - non-recurring - Special - Building grant".

The voucher is herewith returned cancelled together with the bill countersigned.

Ag. Inspector of Schools,
Coorg & Bangalore.

To

The correspondent, Baldwin Boys' High School, Bangalore.

" Treasury Officer, Bangalore.

" Accountant-General, Madras.

Copy to the Secretary to the Hon'ble the Resident in Mysore.

OFFICE OF THE RESIDENT IN MYSORE
BANGALORE.
12 FEB 1936
Regn. No. 1983
Secy. No.

May be filed

27.2.36 T.N.T 27-2-36. Record.